#### 1.0 Objective

The objective of this procedure is to ensure quality of works in all construction projects under taken by the organisation. It is the primary responsibility of contractor to ensure quality in construction and it is the collective responsibility of both construction and quality assurance division to assure quality work, while the former will take care of field works, both the divisions will ensure that the tests are conducted as per BIS specifications in reputed laboratories.

#### 1.1 Application

This procedure is applicable to all the projects entrusted to **KSPH&IDCL** by the client organization for construction.

#### 2.0 Responsibility

Responsibility and Authority for various activities of Quality control is described in procedure part.

#### 3.0 Terms and definitions

- Concession Permission to use or release a product that does not conform to specified requirement.
- Deviation Permit Permission to depart from the originally specified requirements of a product prior to realization.
- 3) **Document –** Information and its supporting medium.
- 4) **Quality Assurance –** Part of quality management focused on providing confidence that quality requirements will be fulfilled.
- 5) **Quality Characteristic –** Inherent characteristic of a product, process or system related to a requirement.

| Revision: 1 | Revision date: 01.07.2015 | Page 1 of 13 |
|-------------|---------------------------|--------------|
|-------------|---------------------------|--------------|

- Record Anything (Such as a document or a photograph) providing permanent evidence of or information about past events; it also includes documents in digital form
- 7) **Requirement –** need or expectation that is stated, generally implied or obligatory.
- 8) **Specification –** Document and stated requirements of the product.
- 9) **Verification –** Confirmation, through the provision of objective evidence, that specified requirements have been fulfilled.

#### 4.0 Procedures

Following abbreviations and terms are used in the table

| D = Document                 | R = Record                          |
|------------------------------|-------------------------------------|
| PR = Procedure               | CL = Check list                     |
| TP = Test procedure          |                                     |
| STD = Relevant BIS           | TR = Test Records                   |
| CE = Chief Engineer          |                                     |
| SE = Superintending Engineer | EE = Executive Engineer             |
| DES = Designs                | QC = Quality control                |
| TP = Third party             | PMC = Project Monitoring Consultant |
|                              |                                     |

PRC = Project review committee consisting of

MD, ED,FA, CE, SE and other designated employees as determined by the MD/ED.

| Revision: 1 | Revision date: 01.07.2015 | Page 2 of 13 |
|-------------|---------------------------|--------------|
|-------------|---------------------------|--------------|

#### 4.1 General :

As all the building materials including electrical fittings etc., required for a project are brought by the Contractors, the procedure part details the tests to be conducted by the Contractors on the same and KSPH&IDCL functionaries has to verify whether these materials conform to the acceptance criteria or not.

#### 4.2 Planning for quality control

Concerned Executive Engineer of a division who is considered as the project manager shall plan for achieving quality in the construction project using the following guidelines. In this endeavor, he shall delegate required responsibilities and authorities to other staff of the division / sub-division to plan and achieve quality.

Quality control planning for a particular project shall include responsibilities and authorities for the following personnel in the project:

- a) Contractor (or his quality control engineer)
- b) PMC/ JE / AE / AEEs of sub-divisions
- c) Executive Engineer of the division

It shall be noted that EE-QC / AEE-QC will be playing role to assist the respective divisions in initiating mid-term course corrective action in order to comply with specifications/ BOQ with regard to project (Buildings) requirements based on their observations during their site visits.

Concerned Executive Engineer of a division may prepare project specific quality plan (example, type of building / construction techniques adapted may require minimal or enhanced control measures to avoid problems)

Project quality plan shall define:

a) Nature of quality control / test activity to be performed

| Revision: 1 | Revision date: 01.07.2015 | Page 3 of 13 |   |
|-------------|---------------------------|--------------|---|
|             |                           |              | 1 |

- b) Personnel responsible to perform the activities
- c) Documents (such as BIS Codes, Bill of quantities, Specifications etc.,)
- d) Personnel authorised to approve the results of tests conducted
- e) Personnel authorised to approve deviations and accord concessions or a suitable disposition
- f) Record requirements

#### 4.3 Informative notes

#### BUILDING MATERIALS AND CONSTRUCTION

The plan may contain more than one means of controlling the quality of various construction materials which may be naturally occurring or produced by the Contractor or obtained from other agencies, for example Coarse aggregates, fine aggregates, bricks etc., The construction materials also includes those manufactured in factories and readily available in open market like cement, Reinforcement steel, electrical materials etc., The Core Plan may describe the methods for controlling and auditing the quality of material procured or produced by the Contractor.

#### 4.4 ELECTRICAL MATERIALS AND CONSTRUCTION

For the purpose of this section, the following definitions apply:

**Electrical Work:** means any work associated with the installation, modification, removal, inspection, or testing of electrical System Components.

#### a) Quality Control of Electrical Items

The EE/AEE – Electrical shall provide guidelines for the project EE / AEE / AE/PMC that describe how the Contractor should carry out quality control for the electrical items and

| Revision: 1 | Revision date: 01.07.2015 | Page 4 of 13 |
|-------------|---------------------------|--------------|
|-------------|---------------------------|--------------|

/or groups of electrical items that are used in a typical construction contract that includes Electrical Work.

### 4.5 Inspection by contractor:

For each electrical item or group of electrical items listed, the Contractor shall identify what inspection will be done. As a minimum, the Contractor shall monitor and inspect the work in accordance with Schedule B specifications.

| SI.No. | Responsibility  | Activity  | D/R | Reference                |
|--------|-----------------|---|-----|--------------------------|
| 1      | EE (Divisional) | To ensure tested materials<br>are used on works and post<br>those Test reports on the<br>website. | R   | Formats F:14-1 to F:14-8 |
| 2      | EEQC & AEEQC    | Verify the Test reports w.r.t materials collected at site on random basis.                        | R   |                          |
| 3      | SE              | To ensure free flow of<br>information between field<br>staff and Head Office                      |     |                          |

### 4.6 General Procedure for Quality Assurance :

SE will inspect the works periodically to ensure compliance to quality. EEQC and AEEQC will independently inspect the works periodically covering most of the major works. Any deviation noticed by EEQC & AEEQC should be communicated to the concerned EE (Divisional) and AEE (Sub divisional) with proposed corrective action. Differences will be completely sorted out at SE level and informed to CE only if his intervention is required. All fines, penalties etc will be levied on the contractors only with specific written instructions / approval from CE or higher authorities.

#### 5.0 Materials

| Revision: 1 | Revision date: 01.07.2015 | Page 5 of 13 |  |
|-------------|---------------------------|--------------|--|
|-------------|---------------------------|--------------|--|

#### Quality Control of Building / Raw Materials:

As all the building materials including electrical fittings etc., required for a project are brought by the Contractors, the procedure part details the tests to be conducted by the Contractors on the same and KSPH&IDCL functionaries has to verify whether these materials conform to the acceptance criteria or not.

| Responsibility for            |                                 |   |  |   |   | е                     |                        |
|-------------------------------|---------------------------------|---|--|---|---|-----------------------|------------------------|
| SI.<br>No.                    | verification of test<br>reports | approval to<br>deviations/<br>Concessions | Material<br>s to be<br>tested                          | Sampling Details  | Frequency of tests  | Permissible<br>limits | Doc / Record Reference |
| 1                             | AEE / AE<br>/ JE/PMC            | CE  | Water  | i)From local source<br>ii)From outside<br>sources                 | i)Once before<br>actual usage<br>ii) As and when<br>the source is<br>changed                        | As per F:14-<br>1     | F:14<br>-1             |
| 2                             | 2 AEE / AE<br>/ JE/PMC CE       |   | Cement   | One sample for every<br>75 tonnes or when the<br>brand is changed | i)Fineness<br>ii)Initial Setting<br>Time<br>iii)Final Setting<br>Time<br>iv)Compressive<br>Strength | As per<br>F:2314-2    | F:14<br>-2             |
| 3                             | AEE / AE<br>/ JE/PMC            | CE  | Reinforc<br>e-ment<br>Steel                            | For every 30 tonnes of same diameter                              | i)Tensile strength<br>ii)Yield stress<br>iii)Percentage<br>elongation                               | As per<br>F:14-3      | F:14<br>-3             |
| 4                             | 4 / JE/PMC CE                   |   | Sand   | For every 100 cum of<br>sand received from<br>the same source     | Grading Zone<br>Analysis<br>Deleterious<br>materials  | As per<br>F:14-4      | F:14<br>-4             |
| 5 / JE/PMC <sub>CF</sub> aggr |                                 | Coarse<br>aggrega<br>te                   | For every 100 cum of<br>CA brought from<br>same source | Test for gradation  | As per<br>F:14-5  | F:14<br>-5            |                        |
| 6                             | AEE / AE<br>/ JE/PMC            | CE  | Burnt<br>clay<br>bricks                                | For every 25,000<br>bricks or when the<br>source / brand is       | i)Water absorption<br>ii)Compressive<br>strength  | As per<br>F:14-6      | F:14<br>-6             |
|                               | Revision: 1                     |   |  | Revision date   | e: 01.07.2015   | Page 6                | of 13                  |

### IMSP 14

# QUALITY CONTROL AND QUALITY ASSURANCE

|            | Responsit                       | oility for                                |                               |   |   |   |                                   | e   |
|------------|---------------------------------|---|-------------------------------|---|---|---|-----------------------------------|---|
| SI.<br>No. | verification of test<br>reports | approval to<br>deviations/<br>Concessions | Material<br>s to be<br>tested | Sampl   | ing Details   | Frequency of tests                                  | Permissible<br>limits             | Doc / Record Reference                        |
|            |                                 |   |                               | changed   |   | iii) Test for<br>Dimensions                         |                                   |   |
| 7          | AEE / AE<br>/ JE/PMC            | CE  | Laterite                      | laterite<br>when t  | very 2000<br>e stones or<br>he source /<br>is changed   | i)Compressive<br>strength<br>ii)Water<br>absorption | As per<br>F:14-7                  | F:14<br>-7                                    |
| 8          | AEE / AE<br>/ JE/PMC            | CE  | Hollow<br>Concret<br>e Blocks | or when   | y 5000 blocks<br>the source /<br>is changed   | Compressive<br>strength                             | As per<br>Agree ment<br>Docu ment | As per<br>IS<br>2185<br>(part-<br>1)-<br>1979 |
| 9          | AEE / AE<br>/ JE/PMC            | CE  | Solid<br>Concret<br>e Blocks  | or when   | y 5000 blocks<br>the source /<br>is changed   | Compressive<br>strength                             | As per<br>Agree ment<br>Docu ment | As per<br>IS<br>2185<br>(part-<br>1)-<br>1979 |
| 10         | AEE / AE<br>/ JE/PMC            | CE  | Concret<br>e Cubes            | Quantity<br>in m <sup>3</sup><br>1-5<br>6-15<br>16-30<br>31-50<br>51 &<br>Above | No. of<br>Samples<br>1<br>2<br>3<br>4<br>4+one<br>additional<br>sample for<br>each 50 m <sup>3</sup><br>or part<br>thereof. | Compressive<br>strength                             | As per<br>F:14-8                  | F:14<br>-8                                    |

| Revision: 1 | Revision date: 01.07.2015 | Page 7 of 13 |
|-------------|---------------------------|--------------|
|-------------|---------------------------|--------------|

# IMSP 14

# QUALITY CONTROL AND QUALITY ASSURANCE

|            | Respons                         | ibility for                               |  |  |  |  | е                      |
|------------|---------------------------------|---|--|--|--|--|------------------------|
| SI.<br>No. | verification of test<br>reports | approval to<br>deviations/<br>Concessions | Material<br>s to be<br>tested  | Sampling Details   | Frequency of<br>tests  | Permissible<br>limits                  | Doc / Record Reference |
| 11         | AEE / AE<br>/ JE/PMC            |   | M.S<br>Door<br>frames,<br>window<br>frames                           | 5 % of the materials to<br>be tested for<br>a. Dimension<br>b. Workmanship<br>c. Fixtures for method<br>of hinging | Physical<br>measurement,<br>Physical<br>observation,<br>Physical<br>verification | As per<br>Agreement                    |                        |
| 12         | AEE / AE<br>/ JE/PM0            |   | Water<br>closets,<br>Wash<br>basins,<br>Urinal<br>basins             | 10 % of the materials<br>to be tested for<br>a. Brand name as per<br>agreement<br>b. ISI marking                   | Physical<br>verification<br>Physical<br>verification                             | As per<br>Agreement /<br>Specification |                        |
| 13         | AEE / AE<br>/ JE/PMC            |   | G.I<br>pipes   | 10 % of the materials<br>to be tested for<br>Specifications  | Physical<br>measurement,<br>Physical<br>measurement<br>Physical<br>observation   | As per<br>Agreement /<br>Specification |                        |
| 14         | AEE /<br>AE /<br>JE/PMC         | CE  | G. I<br>Fittings,<br>Peet<br>valves,<br>CI<br>pipes,<br>PVC<br>pipes | 10 % of the materials<br>to be tested for<br>a. ISI marking<br>b. Brand name<br>(wherever applicable)              | Physical<br>observation<br>Physical<br>observation                               | As per<br>Agreement /<br>Specification |                        |
| 15         | AEE / AE<br>/ JE/PMC            |   | Taps   | 10 % of the materials<br>to be tested for ISI<br>marking   | Physical observation   | As per<br>Agreement /<br>Specification |                        |

| Revision: 1 | Revision date: 01.07.2015 | Page 8 of 13 |
|-------------|---------------------------|--------------|
|             |                           |              |

T

٦

T

#### KSPH&IDCL IMS Procedure

# IMSP 14

# QUALITY CONTROL AND QUALITY ASSURANCE

|            | Responsibility for              |   |   |  |   |  |                        |
|------------|---------------------------------|---|---|--|---|--|------------------------|
| SI.<br>No. | verification of test<br>reports | approval to<br>deviations/<br>Concessions | Material<br>s to be<br>tested                                   | Sampling Details   | Frequency of tests  | Permissible<br>limits                  | Doc / Record Reference |
| 16         | AEE / AE<br>/ JE/PMC            |   | Glazed<br>wall tiles  | 2% of the materials to<br>be tested for<br>a. Dimension<br>b. Uniformity of<br>colour, shade and<br>texture<br>c. Verification of<br>marking on the<br>packing box and tiles | Physical<br>measurement<br>Physical<br>observation<br>Physical<br>observation                                   | As per<br>Agreement /<br>Specification |                        |
| 17         | AEE / AE<br>/ JE/PMC            |   | Ceramic<br>tiles  | 2% of the materials to<br>be tested for<br>a. Dimension<br>b. Uniformity of<br>colour, shade and<br>texture<br>c. Verification of<br>marking on the<br>packing box and tiles | Physical<br>measurement<br>Physical<br>observation<br>Physical<br>observation                                   | As per<br>Agreement /<br>Specification |                        |
| 18         | AEE / AE<br>/ JE/PMC            |   | Eco –<br>Board<br>door<br>shutters<br>/ PVC<br>door<br>shutters | 10% of the materials<br>to be tested for<br>a. Dimension<br>b. Workmanship<br>c. Fixtures<br>d. Manufacturer's test<br>certificate   | Physical<br>measurement<br>Physical<br>observation<br>Physical<br>measurement /<br>Verification<br>Verification | As per<br>Agreement /<br>Specification |                        |
| 19         | AEE / AE<br>/ JE/PMC            |   | Flush<br>shutters<br>for door                                   | <ul><li>10% of the materials</li><li>to be tested for</li><li>a. Dimension</li><li>b. Manufacturer's<br/>test certificate</li></ul>  | Physical<br>observation<br>Physical<br>verification   | As per<br>Agreement /<br>Specification |                        |

| Revision: 1Revision date: 01.07.2015Page 9 of 13 |
|--|
|--|

T

٦

T

#### 6.0 Quality Plan for construction activities:

As all the building construction activities including electrical works etc., are carried out by the Contractors, the procedure part details the documents to be referred by the KSPH&IDCL functionaries to verify whether these works conform to the requirement or not. For the projects costing more than 200 lakhs Quality plan shall be prepared byKSPH&IDCL.

| SI<br>No. | Responsibility             | Activity  | DOCUMENTS INVOLVED  |
|-----------|----------------------------|---|---|
| 1         | PMC /JE / AE /<br>AEE / EE | Excavation of foundation                                      | <ol> <li>Excavation plan / Building plan</li> <li>Specification in the agreement documents</li> </ol> |
| 2         | PMC /JE / AE /<br>AEE / EE | Foundation concreting   | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 3         | PMC /JE / AE /<br>AEE / EE | Random<br>rubble stone<br>masonry and<br>C.R stone<br>masonry | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 4         | PMC /JE / AE /<br>AEE / EE | Brick Masonry<br>work   | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 5         | PMC /JE / AE /<br>AEE / EE | Reinforced<br>cement<br>concrete                              | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 6         | PMC /JE / AE /<br>AEE / EE | Joineries   | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 7         | PMC /JE / AE /<br>AEE / EE | Finishing<br>including<br>plastering and<br>painting works    | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 8         | PMC /JE / AE /<br>AEE / EE | Water Supply<br>works   | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 9         | PMC /JE / AE /<br>AEE / EE | Sanitary works  | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |
| 10        | PMC /JE / AE /<br>AEE / EE | Electrical<br>works   | <ol> <li>Specification in the agreement documents</li> <li>Construction drawings</li> </ol>           |

| Revision: 1 | Revision date: 01.07.2015 | Page 10 of 13 |
|-------------|---------------------------|---------------|
|-------------|---------------------------|---------------|

#### 7.0 Plan for conducting quality control inspection by Quality Control Division

As all the building construction activities including electrical works etc., are carried out by the Contractors and regular supervision on day to day basis are carried out by various functionaries of the construction / electrical Divisions, the procedure part details the inspection plan for the KSPH&IDCLs Quality Control functionaries to verify whether the raw materials / works conform to the requirement or not. If the QC/QA activities are outsourced, then QC exercises required control on the subcontracted agencies as defined in respective work orders.

| SI.<br>No. | Activity                  | Responsibility                       | Description  | Frequency /<br>Duration  |
|------------|---------------------------|--------------------------------------|--|--|
| 1          | Planning of<br>Inspection | EE(QC)                               | a. The QC Division shall plan<br>and schedule the inspections of<br>QC staff for the ongoing works   | Every Month as per<br>approved inspection<br>program   |
|            |                           |                                      | b. The various works required to<br>be inspected by QC staff may<br>also be identified by the Top<br>Management, based on the<br>criticality of works or any other<br>reason                         | As and when<br>directed by the Top<br>Management   |
| 2          | Inspection                | EE(QC)/<br>AEE(QC)/<br>AE(QC)/JE(QC) | a. QC staff shall visit the site of<br>the work to be inspected and<br>conduct inspection of the<br>Building Materials / Test reports<br>/ works   | 10% of the works<br>shall be inspected<br>and as per priority<br>of management               |
|            |                           |                                      | b. Any deviations noticed by QC<br>staff should be communicated to<br>concerned EE/AEE through e-<br>mails / Inspection notes/site<br>instructions with proposed<br>corrective action.               | F : 14-9 /Inspection<br>notes to be issued<br>within 10 days from<br>the date of site Visit. |
| 3          | Action Taken<br>report    | EE ( Division)                       | The concerned EE<br>(Division) shall send action<br>taken report on the QC findings<br>/ observations after attending to<br>the necessary corrective actions<br>to SE with copies to EEQC &<br>AEEQC | Within 15 days from<br>the date of<br>observation / issue<br>of Inspection notes             |

| Revision: 1 | Revision date: 01.07.2015 Page 11 of |
|-------------|--------------------------------------|
|-------------|--------------------------------------|

Third party Quality control Inspection should be carried out for all works contract of estimated value more than Rs200 lakhs and all goods contract costing more than Rs25lakhs. This is as per GOK'S GO No. FD 55Pro.cell 2004 Dtd 17.02.2005. Ref. Contract documents.

#### 8.0 Reference

- a) ISO 9001: 2008 Clause Number 8.2.4
- b) IMS Manual Clause Number 8.2.4

#### 9.0 Associated Documents

- a) Procedure for control of documents IMSP 01
- b) Procedure for control of records IMSP 02
- c) Procedure for control of monitoring and measuring devices IMSP 13
- d) Procedure for control of non conforming products IMSP 15
- e) Procedure for corrective preventive action IMSP 27

| Approved by: Managing Dir | ector                     |               |
|---------------------------|---------------------------|---------------|
| Revision: 1               | Revision date: 01.07.2015 | Page 12 of 13 |

KSPH&IDCL IMS Procedure

# IMSP 14

# QUALITY CONTROL AND QUALITY ASSURANCE

| Revision: 1 | Revision date: 01.07.2015 | Page 13 of 13 |
|-------------|---------------------------|---------------|
|-------------|---------------------------|---------------|